

CITY IMPROVEMENT DIVISION, BANGALORE.

Notice dated 11th February 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, City Improvement Division, Lal-Bagh Road, Bangalore City, up to 4 P.M., on 8th March 1919, for constructing the interior stalls of the New General Market at Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1920.

2. The plans, detailed estimate and conditions may be seen at the Office of the Executive Engineer, City Improvement Division, Bangalore, between the hours of 11 A.M. and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and should be superscribed "Tender for constructing the interior stalls of the New Market at Bangalore City," in default of which, tenders will be rejected:

5. The final acceptance of any tender will rest with the Bangalore City Improvement Committee, which does not bind itself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which, his tender will be considered cancelled, and his earnest money forfeited.

7. The name of the competitor, whose tender is accepted, will be posted in the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of the tender will receive reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing the interior stalls of the New General Market in Bangalore City.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork, excavating foundation and filling in basement ...	C. yds.		1,480	
2	Burnt jelly concrete in mortar ...	C. ft.		8,711	
3	Burnt stone in mortar foundation and basement with bond stones ...	"		27,821	
4	Size stone in mortar superstructure with necessary bond stones...	"		20,105	
5	Archwork stone in mortar ...	"		186	
6	Burnt stone slabs 4" to 6" thick exposed parts of plinth slabs, 2 lines dressed and all the rest roughly dressed.	S. ft.		34,288	
7	Burnt stone slabs 4" to 6" thick exposed parts of plinth slabs 2 lines dressed and all the rest roughly dressed including shap- ing to the required curve.	"		3,192	
8	Pointing with cement ...	Sq.		190.24	
9	Pointing with chunam ...	"		137.69	
10	Cement pointing the partition slabs ...	"		251.75	
11	One line dressed stone pillars 8" x 8" x 8'-10" with caps including fixing with lead, iron peg, etc., complete.	Each		672	
12	One line dressed stone pillars, 8" x 8" x 10'-4" with caps including fixing with lead, iron peg, etc., complete.	"		164	
13	One line dressed stone pillars, 8" x 8" x 10'-6" with caps including fixing with lead, iron peg, etc., complete.	"		8	
14	One line dressed stone pillars, 8" x 8" x 10'-10" with caps includ- ing fixing with lead, iron peg, etc., complete.	"		29	
15	One line dressed stone pillars, 9" x 9" x 10'-4" with caps including fixing with lead, iron peg, etc., complete.	"		33	
16	One line dressed stone pillars, 9" x 9" x 10' with caps including fixing with lead, iron peg, etc., complete.	"		20	
17	Reinforced concrete pillars, 9" x 9" x 10'-4" with caps including fixing.	"		12	
18	Do do 9" x 9" x 10'-10" do	"		2	
19	Do do 9" x 9" x 11'-4" do	"		2	
20	Do do 9" x 9" x 12'-4" do	"		54	
21	Dressed stone beams and bressummers including hoisting and fixing with cement.	C. ft.		2,716	
22	Dressed stone beams and bressummers including hoisting and fixing with cement and also including shapings to the required curve.	"		185	
23	Teakwood doors panelled with iron fittings, paintings, etc., com- plete.	S. ft.		1,716	
24	Teakwood doors panelled with expanded metal at top, iron fittings painting, etc., complete.	"		672	
25	Teakwood doors panelled with expanded metal at top and bottom, iron fittings, painting, etc., complete.	"		540	
26	Teakwood ventilators with glazed shutters, iron bars, painting, etc., complete.	"		308	
27	Teakwood ventilators with expanded metal shutters permanently fixed, painting, etc., complete.	"		60	
28	Expanded metal shutters with angle iron frames, bolts, nuts, etc., complete.	"		596	
29	Teakwood ventilators, panelled with iron bars, painting, etc., complete.	"		140	
30	Preparing and fixing sun shades (8½' x 3½') of asbestos sheets with stone brackets, wood work painting, etc., complete.	Each		12	
31	Teakwood queen post trusses 34' span including painting, etc., complete.	"		4	
32	Teakwood queen post trusses 20' span including painting, etc., complete.	"		8	

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
33	Teakwood wrought and put up including wood oiling 2 coats	C. ft.		259	
34	Teakwood planks 1" thick	S. ft.		60	
35	Roofing with 4" to 4½" thick slabs and 4½" concrete including grouting the joints with cement concrete plastering with chunam above and cement pointing below.	Sq.		368'03	
36	Roofing with 1st class Masalore tiles on teak reapers	"		24'49	
37	Roofing with pukka terrace with brick on edge flat tiles, plastering, etc., complete.	"		4'13	
38	Ridge tile set in mortar	R. ft.		160	
39	Constructing dormer windows glazed with wood work, roofing, etc., complete.	Each		4	
40	Plain slabbed cornice with concrete slope above including cement plastering. Projection 1½ foot from wall.	R. ft.		899	
41	Plain slabbed cornice with concrete slope above including cement plastering. Projection 2½ feet from breastsummer.	"		1,553	
42	Brick masonry cornice 12" thick including cement plastering	"		917	
43	Do dental cornice 12" thick with cement plastering	"		147	
44	Slabbed parapet wall with bottom slab resting on stone seats and top slab complete fixed in cement as per design.	"		2,308	
45	Constructing brick masonry or concrete pillars, 9" x 9" x 2½' with caps including cement plastering complete.	Each		393	
46	Brick masonry parapet wall 4½" thick 1'-9" high with pillars and cement plastering, complete.	R. ft.		1,003	
47	Filling in earth and forming platform with good consolidation	C. yds.		494	
48	Reinforced concrete slabs	S. ft.		1,296	
49	Flooring with 2" cement concrete over 2½" ordinary concrete	Sq.		320'21	
50	Ornamental cast stone brackets	Each		30	
51	Cutting the corners of slabs (in fruit stalls)	Per stall		20	
52	Cutting grooves in pillars	R. ft.		141	
53	Providing cross slab (roughly dressed) over drain	S. ft.		2,517	
54	Providing iron hooks	Each		695	
55	Preparing and fixing expanded metal revolving meat safes	"		48	
56	Do poultry cage with asbestos sheets at top and for horizontal partitions and expanded metal for front and sides with painting as per design.	R. ft.		78	
57	Ornamental cast iron railings with finials, etc., complete	L. S.			
58	Providing galvanised zinc water down pipes 3" diameter including bends, etc., complete.	R. ft.		67	
59	Finishing the wall above breastsummer with mortar panels, cornice, etc., complete.	L.S.			
60	Constructing compound wall 6' high from ground	R. ft.		1,250	
61	Do 5½' do	"		163	
62	Do 4½' do	"		970	
63	Providing wrought iron gates	Each		4	
64	Constructing U shaped concrete drain with cement plastering, side and top slabs, complete.	R. ft.		4,250	
65	Forming road 24' wide with 9" thick gravel	R. yd.		180	
66	Do 15' 9" do	"		261	
67	Do 9' 6" thick gravel	"		1,000	
68	Providing glass tiles to main entrance	Each		40	

Note—For stone in mortar, the stones obtained from dismantling the Fort wall may be utilized.

K. P. PUTTANNA CHETTY,
Chairman.

CHITALDRUG DISTRICT.

Notice dated January 1919.

Notice is hereby given that an application has been received from one Bhima Rao, Shanbhog for the grant of the Bechirak Arasur village site, Chitaldrug Taluk for cultivation on ordinary assessment in force in the locality. Persons desirous of bringing in fresh settlers to the village or of otherwise repopulating the village may apply to the undersigned within three months of the date of this notice.

C. B. LAKSHMANA RAO,
For Deputy Commissioner.

THE BANGALORE WOOLLEN, COTTON AND SILK MILLS Co., LTD.

Notice dated 12th February 1919.

The transfer books of the Company will be closed from the 17th to 24th February 1919, both days inclusive.

By order of the Directors,
Binny & Co., Ltd.,
J. W. CHAMBERS,
Manager,

Agents, Secretaries and Treasurers,
The Bangalore Woollen, Cotton and Silk Mills Co., Ltd.